

TEST RESULTS

INTENDED FOR INFORMATION ONLY

(Applies only to U.S. products)

This is to state that **SuperArc® L-59®** electrode was tested in accordance with the following welding procedure.

Operating Settings	Results
Electrode Size (inches)	0.045
Polarity	DC+
Shielding Gas (per AWS A5.32)	100% CO ₂ (C1-C-100)
Voltage V	30
Wire Feed Speed cm/min (in/min)	1092 (430)
Current amps	290
Contact Tip to Work Distance mm (in.)	19 (3/4)
Passes/Layers	16/6
Preheat Temp °C (°F)	20 (70)
Interpass Temp °C (°F)	150 (300)

Mechanical properties of the weld deposit (in the as-welded condition) were as follows:

Tensile Strength MPa (ksi)	540 (79)
Yield Strength, 0.2% offset MPa (ksi)	440 (63)
Elongation (%)	22
Average Hardness Rockwell B	86
Charpy V-notch Impact Properties Avg.	61 (45)
Joules @ -40 °C (ft-lbf @ -40 °F)	43,68,73 (32,50,54)
Charpy V-notch Impact Properties Avg.	88 (65)
Joules @ -29 °C (ft-lbf @ -20 °F)	78,92,94 (58,68,69)

Chemical composition


(weight %)	Electrode	Deposit
C	0.07	0.09
Mn	1.49	1.11
Si	0.85	0.58
S	0.019	0.018
P	0.005	0.005
Cr	0.03	0.03
Ni	0.02	0.02
Mo	0.00	0.01
V	0.00	0.00
Cu (Total)	0.16	0.17

Test assembly constructed of ASTM A36 steel. Joint design per AWS A5.18-2005.

Charpy Impact averages calculated per AWS A5.18.

Results below the detection limits of the instrument or lower than the precision required by specification are reported as zero. Strength values in SI units are reported to the nearest 10 MPa converted from actual data. Preheat and interpass temperature values in SI units are reported to the nearest 5 degrees.


 27 March 2015
 David A. Fink, Manager, Compliance Engineering,
 Consumable R&D Department, Date


 3/27/15
 Toronto Cunningham,
 Certification Supervisor, Date